BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P. Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to: **Original/Duplicate**

Name of Work :- Construction of RCC Drains and RCC Culverts at Right Side Cross Roads of 1st Main Road Kuvempu Nagara in Ward No.05

Sl. No.	Qty	Description	Unit	Rates	
				In Figures	In Words
1	955.90	KSRRB 300-3. **Earthwork excavation by manual means** for roads, drains & similar works in ordinary soil invoiving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification with all lead and left as per directions of engineer in charge of the work.	Cum	207.60	Rupees Two Hundred Seven And Paise Sixty Only
2	143.39	KSRRB M2100-10. Providing and laying **Plain cement concrete of mix 1:3:6** with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. with all lead and left as per directions of engineer in charge of the work.	Cum	5509.33	Rupees Five Thousand Five Hundred Nine And Paise Thirty Three Only
3	317.01	Providing and laying plain/reinforced cement concrete for side drains **using M20 nominal mix** concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm with all lead and left as per directions of engineer in charge of the work.	Cum	7189.42	Rupees Seven Thousand One Hundred Eighty Nine And Paise Forty Two Only

	Qty	Description	Unit	Rates	
				In Figures	In Words
4	20.95	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C workincluding straightening, cutting, bending, hooking, placing in position,lapping and / or welding wherever required, tying with binding wire andanchoring to the adjoining members wherever necessary complete asper design (laps, hooks and wastage shall not be measured and paid)cost of materials, labour, HOM of machinery complete as perspecifications. with all lead and left as per directions of engineer in charge of the work.	Tonne	72326.98	Rupees Seventy Two Thousand Three Hundred Twenty Six And Paise Ninety Eight Only
5	748.80	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. with all lead and left as per directions of engineer in charge of the work.	Sqm	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only
6	35.22	Providing and fixing Precast RCC slab of 250mm thick for Culverts made of Plain/Reinforced Cement Concrete design mix M25 with OPC@340kgs,with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregates@0.47cum,with superplasticizer@3lts confirming to 189103-1999 Reaffirmed-2008,Open Foundation complete as per Drawing and Technical Specification including cost of all materials, labour,HOM curing,form works,scaffolding and centering complete as per specifications and pointing for ljoints 1:3 cement mortar including form work,lift charges,curing and concrete finished surfaces on both sides etc,complete with all lead and left as per directions of engineer in charge of the work.	Sqm	5418.00	Rupees Five Thousand Four Hundred Eighteen Only

Executive Engineer
Byatarayanapura Division
B.B.M.P. Bangalore - 92

Note:

1 Item for Which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of Quantities (refer:ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))